


本圖完工後請速歸還

流水號:227

HOLD!



FOR CONSTRUCTION

JUL. 15, 2025

□ 管件序號 <1> 直管編號 [1] 管段編號 & 須設計會驗管線			資料庫 名稱：		工廠焊接 套焊 螺紋銜接 配合現場焊接 配合現場接合點 管支撐 蒸汽追蹤管 —						
---------------------------------------	--	--	------------	--	--	--	--	--	--	--	--

FABRICATION MATERIALS				
PT NO	COMPONENT DESCRIPTION	N.S. (INS)	ITEM CODE	QTY
PIPE				
1	PIPE A312-TP304 EFW SCH40S PE CNS 6331	1/2	S1P1F/P-1/2"-40S	1.2M
FITTINGS				
2	TEE 3000# SW A182-F304 ASME B16.11	1/2 x 1/2	S1P1F/TS-1/2"	1
FLANGES				
3	FLANGE SW 150# RF A182-F304 SCH40S BORE ASME B16.5	1/2	S1P1F/FRSW-1/2"	1
ERECTION MATERIALS				
PT NO	COMPONENT DESCRIPTION	N.S. (INS)	ITEM CODE	QTY
FLANGES				
4	FLANGE BLIND 150# RF A182-F304 ASME B16.5	1/2	S1P1F/FBR-1/2"	1
GASKETS				
5	GASKET 150# RF 4.5 MM THICK 304SS SPIRAL WOUND W/GRAPHITE FILLER W/SS304 OUTER RING ASME B16.20/B16.5	1/2	S1P1F/GR-1/2"	1
BOLTS				
6	STUD BOLT A193 GR.B8 W/ TWO HEX. HEAD HEAVY NUT A194 GR.8 ASME B1.1 B18.2.2	1/2	S1P1F/BS4-1/2"X60L	4
INSTRUMENTS				
7	MANUAL CONTROL STATION (BY OTHER)	1/2	S1P1F/AVH-1/2"	1
SUPPORTS				
8	U-BOLT (UBA-1/2)	1/2	SUP/UBA-1/2"	1
9	AUXILIARY SUPPORT (AS12A-06)	1/2	SUP/AS12A-1/2"	1
10	GROUT (GR2-3)	1/2	SUP/GR2-1/2"	1

CUT PIPE LENGTH FOR REFERENCE ONLY						
PIECE NO	CUT LENGTH	N.S. (INS)	REMARKS	PIECE NO	CUT LENGTH	N.S. (INS)
<1>	260	1/2		<2>	95	1/2
<3>	75	1/2		<4>	719	1/2

△				
△				
0	2025.07.15	FOR CONSTRUCTION	陳至鉉	陳逢明
A	2025.04.21	FOR APPROVAL	陳至鉉	陳逢明
序次	日 期	修 改 說 明	修 改	認 可