


本圖完工後請速歸還


[illegible]

ERECTION MATERIALS				
PT NO	COMPONENT DESCRIPTION	N.S. (INS)	ITEM CODE	QTY
FLANGES				
1	FLANGE BLIND 150# RF A182-F304 ASME B16.5	4	S1P4/FBR-4"	1
GASKETS				
2	GASKET 150# RF 3.0 MM THICK VIRGIN PTFE ZW#7500 ASME B16.21/B16.5	4	S1P4/GR-4"-ZW#7500	2
BOLTS				
3	STUD BOLT A193 GR.B8 W/ TWO HEX. HEAD HEAVY NUT A194 GR.8 ASME B1.1 B18.2.2	5/8	S1P4/BS4-5/8"X95L	16
VALVES / IN-LINE ITEMS				
4	BALL 150# RF A351-CF8/304SS+PTFE FULL PORT FIRE SAFE WRENCH OPER. ASME B16.34 (VOC<100 vppm)	4	S1P4/VA-4"-4144-E	1
SUPPORTS				
5	FLANGE GROUNDING CONDUCTOR (C-501)	4	MISC/C-501	2



**FOR CONSTRUCTION**

**JUL. 04, 2025**

										管線編號 TRIM-TK611-N6D-4"-S1P4									
□ 管件序號    <1> 直管編號    [1] 管段編號 & 須設計會驗管線			資料庫 名稱：		工廠焊接   套焊   螺紋銜接   配合現場焊接   配合現場接合點   管支撐   蒸汽追蹤管 —— —E—E—   —X—   —■—   —=—   —. .			Eshine   鴻勝化學科技股份有限公司 E-shine Advanced Chemicals Ltd.											
操作壓力: 0.05 $\frac{KG}{CM^2} G$		操作溫度: 38   °C		管線等級:        S1P4		製   圖		陳怡如		2025.04.21		會 簽			 富台工程股份有限公司 FU-TAI ENGINEERING CO., LTD.				
設計壓力: 0.14 $\frac{KG}{CM^2} G$		設計溫度: 80   °C		保溫(冷)等級:		設   計		黃炳富		2025.04.21									
試驗基準: Air		0.18 $\frac{KG}{CM^2} G \times 60$ 分		熱追蹤等級:		審   核		陳安誠		2025.04.21									
管路塗裝:		管 材 塗 裝		焊接基準:		認   可		陳達明		2025.04.21									
焊道: 塗裝:		碳鋼及不銹: 鋼保溫(冷): 不銹鋼:		NDE 抽驗:    10 %		依據圖號: C2418-4-512				圖號:		檔號: TRIM-TK611-N6D-S1P4-   1							
														審尾一期 建廠工程		管線工程 立體配管圖		<div>1</div> <div>1</div>	