


本圖完工後請速歸還

ERECTION MATERIALS

PT NO	COMPONENT DESCRIPTION	N.S. (INS)	ITEM CODE	QTY
FLANGES				
1	FLANGE BLIND 150# RF A182-F304 ASME B16.5	3	S1P4/FBR-3"	1
GASKETS				
2	GASKET 150# RF 3.0 MM THICK VIRGIN PTFE ZW#7500 ASME B16.21/B16.5	3	S1P4/GR-3"-ZW#7500	2
BOLTS				
3	STUD BOLT A193 GR.B8 W/ TWO HEX. HEAD HEAVY NUT A194 GR.8 ASME B1.1 B18.2.2	5/8	S1P4/BS4-5/8"X95L	8
VALVES / IN-LINE ITEMS				
4	BALL 150# RF A351-CF8/304SS+PTFE FULL PORT FIRE SAFE WRENCH OPER. ASME B16.34 (VOC<100 vppm)	3	S1P4/VA-3"-4144-E	1
SUPPORTS				
5	FLANGE GROUNDING CONDUCTOR (C-501)	3	MISC/C-501	2



N



FOR CONSTRUCTION

JUL. 04, 2025

管線編號  
TRIM-TK618-N6A-3"-S1P4

E-shine 鴻勝化學科技股份有限公司  
E-shine Advanced Chemicals Ltd.

富台工程股份有限公司  
FU-TAI ENGINEERING CO., LTD.

管線工程  
立體配管圖

1  
1

檔號: TRIM-TK618-N6A-S1P4- 1

管件序號 <1>直管編號 [1] 管段編號  
& 須設計會驗管線

資料庫名稱:

工廠焊接 套焊 螺紋銜接 配合現場焊接 配合現場接合點 管支撐 蒸汽追蹤管  
— —E—E— X —■— — —

操作壓力: 0.05  $\frac{KG}{CM^2}$  G 操作溫度: 38 °C

管線等級: S1P4

製圖 陳怡如 2025.04.21

會  
簽

設計壓力: 0.14  $\frac{KG}{CM^2}$  G 設計溫度: 80 °C

保溫(冷)等級:

設計 黃炳富 2025.04.21

試驗基準: Air 0.18  $\frac{KG}{CM^2}$  G X 60 分

熱追蹤等級:

審核 陳安誠 2025.04.21

管路塗裝:

管支撐

焊接基準:

認可 陳逢明 2025.04.21

焊道: 塗裝

管材料塗裝  
碳鋼及不銹鋼保溫(冷): 不銹鋼

NDE 抽驗: 10 %

依據圖號: C2418-4-514

圖號:

△					
△					
△	2025.07.03	FOR CONSTRUCTION	黃炳富	陳逢明	
△	2025.04.21	FOR APPROVAL	黃炳富	陳逢明	
序次	日期	修改說明	修改	認可	