


本圖完工後請速歸還

流水號:677

FABRICATION MATERIALS				
PT NO	COMPONENT DESCRIPTION	N.S. (INS)	ITEM CODE	QTY
PIPE				
1	PIPE A312-TP304 EFW SCH10S BE ASME B36.19M	4	S1P1/P-4"-10S	0.3M
2	PIPE A312-TP304 EFW SCH40S PE ASME B36.19M	1	S1P1/P-1"-40S	1.6M
FITTINGS				
3	REDUCER ECC BW A403-WP304 SMLS SCH10S/SCH40S ASME B16.9	4 x 2	S1P1/RE-4"X2"	2
4	SOCKOLET 3000# SW A182-F304 MSS SP-97	4 x 1	S1P1/SOL-4"X1"	1
5	SWAGE ECC BLE/PSE A403-WP304 SMLS SCH40S MSS-SP-95	2 x 1	S1P1/SE-2"BX1"P	2
6	90 ELBOW 3000# SW A182-F304 ASME B16.11	1	S1P1/ES-1"X90	2
7	FULL COUPLING 3000# SW A182-F304 ASME B16.11	1	S1P1/CFS-1"	1
FLANGES				
8	FLANGE SW 150# RF A182-F304 SCH40S BORE ASME B16.5	1	S1P1/FRSW-1"	2
ERECTION MATERIALS				
PT NO	COMPONENT DESCRIPTION	N.S. (INS)	ITEM CODE	QTY
GASKETS				
9	GASKET 150# RF 4.5 MM THICK 304SS SPIRAL WOUND W/GRAPHITE FILLER W/SS304 OUTER RING ASME B16.20/B16.5	1	S1P1/GR-1"	1
BOLTS				
10	STUD BOLT A193 GR.B8 W/ TWO HEX. HEAD HEAVY NUT A194 GR.8 ASME B1.1 B18.2.2	1/2	S1P1/BS4-1/2"X65L	4
INSTRUMENTS				
11	TEMPERATURE GAUGE 150# RF TG 61111	1		1
SUPPORTS				
12	FLANGE GROUNDING CONDUCTOR (C-401)	1	MISC/C-401	1
13	AUXILIARY SUPPORT (AS4-0203)	1	SUP/AS4-1"	1
14	CRADLE SHOE (C-1-60)	1	SUP/C-1"-60	1

CUT PIPE LENGTH FOR REFERENCE ONLY							
PIECE NO	CUT LENGTH	N.S. (INS)	REMARKS	PIECE NO	CUT LENGTH	N.S. (INS)	REMARKS
<1>	191	1		<2>	654	1	
<3>	547	1		<4>	176	1	
<5>	300	4					



FOR CONSTRUCTION

JUL. 04, 2025

管線編號

P-61114-1"-S1P1-C60


Eshine 鴻勝化學科技股份有限公司
E-shine Advanced Chemicals Ltd.

富台工程股份有限公司
FU-TAI ENGINEERING CO., LTD.

管線工程
立體配管圖

第 1 期
建廠工程

檔號: P-61114-S1P1- 1

1 管件序號 <1>直管編號 [1] 管段編號 & 須設計會驗管線			資料庫 名稱：		工廠焊接 套焊 螺紋銜接 配合現場焊接 配合現場接合點 管支撐 蒸汽追蹤管 						
操作壓力: 0.05 $\frac{KG}{CM^2}$ G 操作溫度: -16 °C			管線等級: S1P1		製 圖 陳怡如		2025.04.21		會 簽		
設計壓力: 2/-0.1 $\frac{KG}{CM^2}$ G 設計溫度: 80/-26 °C			保溫(冷)等級: C60		設 計 黃炳富		2025.04.21				
試驗基準: Air 2.2 $\frac{KG}{CM^2}$ G X 60 分			熱追縱等級:		審 核 陳安誠		2025.04.21				
管路塗裝:		管 材 塗 裝	焊接基準:		認 可 陳逢明		2025.04.21				
焊道: 塗裝:		碳鋼及不銹: 鋼保溫(冷): 不銹鋼:	NDE 抽驗: 10 %		依據圖號: C2418-4-512				圖號:		

△				
△				
0	2025.07.03	FOR CONSTRUCTION	黃炳富	陳逢明
A	2025.04.21	FOR APPROVAL	黃炳富	陳逢明
序次	日 期	修 改 說 明	修 改	認 可